

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-017-20856-00-00  
Spot: NWESWNW Sec/Twnshp/Rge: 13-18S-6E  
1380 feet from N Section Line, 810 feet from W Section Line  
Lease Name: LOWE HORN Well #: 15-13  
County: CHASE Total Vertical Depth: 1502 feet

Operator License No.: 5192  
Op Name: SHAWMAR OIL & GAS CO., INC.  
Address: 1116 E MAIN PO BOX 9  
MARION, KS 66861

SURF Size: 8.625 feet: 205

*# 4882*

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/11/2004 11:00 AM  
Plug Co. License No.: 5192 Plug Co. Name: SHAWMAR OIL & GAS CO., INC.  
Proposal Rcvd. from: JIM CLOTHIER Company: SHAWMAR OIL & GAS CO., INC. Phone: (620) 383-2932

Proposed Plugging Method: Fill hole with heavy mud & spot cement through the drill pipe. Spot 50 sxs. cement @ 1,490', spot 35 sxs. cement @ 750', and circulate cement from 250' to the surface.

Plugging Proposal Received By: JACK LUTHI Witness Type: NONE  
Date/Time Plugging Completed: 03/11/2004 2:00 PM KCC Agent: MICHAEL WILSON

**RECEIVED  
KCC DISTRICT #2  
AUG 11 2004  
WICHITA, KS**

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

Filled hole with heavy mud & spotted cement through the drill pipe. Spotted 25 sxs. cement @ 1,490', spotted 10 sxs. cement @ 750', and circulated 80 sxs. cement from 270' to the surface.

**RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 31 2004  
CONSERVATION DIVISION  
WICHITA, KS**

Remarks: USED 60/40 POSMIX W/4% GEL BY BLUE STAR ACID SERVICES. INVOICE #5353.

Plugged through: DP

District: 02

Signed Michael Wilson  
(TECHNICIAN)

**INVOICED**  
DATE 8-31-04  
2005040477