

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-00740-00-00  
Spot: SWNW Sec/Twnshp/Rge: 34-16S-10W  
3300 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: SCHROEDER C Well #: 3  
County: ELLSWORTH Total Vertical Depth: 3275 feet

Operator License No.: 30364  
Op Name: RESOURCE OPERATIONS, INC.  
Address: BOX 9487  
TULSA, OK 74157

PROD Size: 5.5 feet: 3251 100 SX CMT  
SURF Size: 8.625 feet: 333 125 SX CMT

\$ 106<sup>44</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/18/2004 9:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Plugging Method: See actual report.

RECEIVED  
KCC DISTRICT #2  
AUG 25 2004  
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER

Witness Type: PARTIAL

Date/Time Plugging Completed: 08/18/2004 11:00 AM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2930' and put 5 sacks of cement on top. Perforated at 1300', 1000' and 380'. Ran tubing to 1300' and pumped 35 sacks of cement. Pulled tubing to 1000' and pumped 35 sacks of cement. Pulled tubing to 380' and circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3049	3055		
3032	3038		
2985	2990		

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 31 2004  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND CEMENT #24806

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

8-31-04

WEL. NO.

2005060476