

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-22852-00-00  
Spot: S2NENW Sec/Twnshp/Rge: 33-19S-11W  
4290 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: PFAFF Well #: 3  
County: BARTON Total Vertical Depth: 3698 feet

Operator License No.: 7383  
Op Name: BOLDING, GRADY CORPORATION  
Address: PO BOX 486  
ELLINWOOD, KS 67526

PROD Size: 5.5 feet: 3449 100 SX CMT  
SURF Size: 8.625 feet: 269 225 SX CMT

*120'19*

Well Type: SWD UIC Docket No: D21302.0 Date/Time to Plug: 08/18/2004 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: GRADY BOLDING Company: BOLDING, GRADY CORPORATION Phone: (620) 564-2240

Proposed Plugging Method: Ordered 525 sxs 60/40 pozmix - 10% gel - 1100# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/18/2004 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied tied onto 5 1/2" casing with a swedge - pumped 200 sxs cement with 600# hulls mixed in.  
Tied onto backside and pumped 100 sxs 60/40 pozmix.  
Tied back on to 5 1/2" casing - pumped 225 sxs 60/40 pozmix with 500# hulls.  
Max. P.S.I. 50#. S.I.P. 0#.  
Topped off with 3/4 yard cement mixture.

Perfs:

Top	Bot	Thru	Comments
3450	3698		

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 31 2004  
CONSERVATION DIVISION  
WICHITA, KS

RECEIVED  
AUG 31 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY - TICKET 17061.

Plugged through: CSG

District: 04

Signed

*[Signature]*  
(TECHNICIAN)

INVOICED

DATE

8-31-04

INV. NO.

2005060451

Form CP-2/3

AUG 26 2004

ISERN-SCHULTZ OIL & GAS, INC.

BOX 486

#3 PFAFF

33-19-11W  
C S/2 NE NW

ELLINWOOD, KS 67526

CONTR WOODMAN-LANNITTI DRLG. CITY BARTON

GEOL \_\_\_\_\_ FIELD ELLINWOOD NORTH

E 1785 KB CM 7/27/82 <sup>CARD</sup> ISSUED 1/6/83 IP SWDW  
ARB OH 3449-3698

API 15-009-22,852

+	+
+	+
+	+

LOG	Tops	Depth/Datum	
			8 5/8 " 269/225SX, 5 1/2 " 3449/100SX
ANH	546	1239	DST (1) 3434-3450 (ARB) / 30-30-30-30, REC 10' OIL SPTD M, SIP 844-470#, FP 45-45 / 45-45#
HEEB	2929	1144	
TOR	2946	1161	DST (2) 3352-3366 (ARB) / 45-45-45-45, REC 50' OIL, 50' OCMW, 60' SOCMW, 120' MW, SIP 966-898#, FP 57-103 / 137-160#
DOUG	2962	1177	
BR LM	3052	1267	DST (3) 3370-3377 (ARB) / 30-30-30-30, REC 360' SW, SIP 966-898#, FP 23-100 / 137-160#
LANS	3072	1287	
BKC	3322	1537	DST (4) 3358-3364 (ARB) / 45-45-45-45, REC 30' OIL, 125' MCO, SIP 969-916#, FP 23-46 / 61-76#
ARB	3334	1549	
RTD	3450	1665	MICR - CO, PF (ARB) 3358-3362, AC 250G, TSTD NON-COMMER-CIAL, SET BP AT 3347, PF (ARB) 3340-3344, AC 250G, TSTD NON-COMMER-CIAL, SQZ'D W / 70 SX, DD TO 3698, SWB 8 BW PER PULL, AC 1000G, SWB 85 BWPH / 4 HRS, PRODUCTION NON-COMMER-CIAL, CONVERTED TO SWDW - INJECTION RATE SATISFACTORY
DDTD	3698	1913	

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS