

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-00147-00-00
Spot: S2SWNESE Sec/Twnshp/Rge: 11-27S-40W
1365 feet from S Section Line, 1275 feet from E Section Line
Lease Name: HELPER Well #: 1
County: STANTON Total Vertical Depth: 2315 feet

Operator License No.: 5952 CIBP Size: feet: 2193 WITH 2 SX CMT
Op Name: BP AMERICA PRODUCTION COMPANY PROD Size: 7 feet: 2240 WITH 600 SX CMT
Address: 2225 WEST OKLAHOMA AVENUE SURF Size: 10.75 feet: 585 WITH 420 SX CMT
ULYSSES, KS 67880

\$75²⁴

Well Type: GAS UIC Docket No: Date/Time to Plug: 08/19/2004 9:00 AM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Rcvd. from: KEVIN STRUBE Company: BP AMERICA Phone: (620) 356-6955

Proposed Plugging Method: CIBP @ 2193' WITH 2 SX CMT. PERFORATE @ 600'. PUMP 240 SX CMT. PRESSURE TEST. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/19/2004 1:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

TEMP. SURVEY SHOWS TOC @ 650'. SET CIBP @ 2193' WITH 2 SX CMT. PERFORATE 7" @ 600'. PUMP 240 SX CMT DOWN 7". PRESSURE TO 100 PSIG & SHUT IN. DID NOT CIRCULATE. PUMP 40 SX CMT DOWN BACKSIDE. PRESSURE TO 50 PSIG. CMT COMING OUT OF SLIPS. SHUT IN.

Perfs:

Top	Bot	Thru	Comments
2221	2315		SLOTTED LINER

RECEIVED
AUG 30 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
AUG 24 2004
KCC Dodge City

Signed

Jim Holland
(TECHNICIAN)

INVOICED
DATE 8-31-04
INV. NO. 2005060453

form 2/3