

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-00350-00-00
Spot: SENENW Sec/Twnshp/Rge: 36-28S-40W
3997 feet from S Section Line, 2673 feet from E Section Line
Lease Name: HEITZMAN GAS UNIT Well #: 2
County: STANTON Total Vertical Depth: 2410 feet

Operator License No.: 5952 PROD Size: 5.5 feet: 2410 WITH 600 SX CMT
Op Name: BP AMERICA PRODUCTION COMPANY SURF Size: 8.625 feet: 686 WITH 400 SX CMT \$7833
Address: 2225 WEST OKLAHOMA AVENUE
ULYSSES, KS 67880

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/17/2004 8:00 AM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Rcvd. from: KEVIN STRUBE Company: BP AMERICA Phone: (620) 356-6955

Proposed Plugging Method: PUMP HULLS & FILL 5 1/2" WITH CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/17/2004 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 2398'. PUMP 700# HULLS MIXED IN CMT TO PLUG PERFS. PUMP 345 SX
TOTAL CMT TO FILL 5 1/2" FROM BOTTOM TO TOP. BACKSIDE CIRCULATED &
CMT VISIBLE AT SURFACE. MAXIMUM PRESSURE 500 PSIG. SHUT IN PRESSURE
400 PSIG.

Perfs:


Top	Bot	Thru	Comments
2378	2388		
2311	2348		
2283	2295		

RECEIVED
AUG 30 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Jim Holland
(TECHNICIAN)

INVOICED
DATE 8-31-04
INV. NO. 2005060453

Form CH 102