

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-187-00141-00-00  
Spot: NENESW Sec/Twnshp/Rge: 1-27S-40W  
2507 feet from S Section Line, 2690 feet from E Section Line  
Lease Name: VATH Well #: 1  
County: STANTON Total Vertical Depth: 2419 feet

Operator License No.: 5952 PROD Size: 7 feet: 2334 WITH 575 SX CMT  
Op Name: BP AMERICA PRODUCTION COMPANY SURF Size: 10.75 feet: 523 WITH 420 SX CMT  
Address: 2225 WEST OKLAHOMA AVENUE  
ULYSSES, KS 67880

4 78 67

Well Type: GAS UIC Docket No: Date/Time to Plug: 08/17/2004 1:00 PM

Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES

Proposal Rcvd. from: KEVIN STRUBE Company: BP AMERICA Phone: (620) 356-6955

Proposed Plugging Method: PUMP 700# HULLS. PUMP CMT TO FILL 7" FROM TOP TO BOTTOM. PRESSURE TEST. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/17/2004 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 700# HULLS MIXED WITH CMT TO PLUG SLOTTED LINER. PUMP 398 SX TOTAL CMT TO FILL 7" FROM BOTTOM TO TOP. PRESSURE TO 480#. SHUT IN PRESSURE 400#. PUMP 50 SX CMT DOWN ANNULUS. PRESSURE TO 300# & SHUT IN.

Perfs:

Top	Bot	Thru	Comments
2325	2419		SLOTTED LINER

RECEIVED  
AUG 30 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED  
AUG 24 2004  
KCC Dodge City

Signed

Jim Holland  
(TECHNICIAN)

INVOICED  
DATE 8-31-04  
INV. NO. 200506045-3

Form 08/03