

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-20132-00-00
Spot: SW Sec/Twnshp/Rge: 35-28S-37W
1320 feet from S Section Line, 1320 feet from W Section Line
Lease Name: STUBBS A Well #: 2
County: GRANT Total Vertical Depth: 2877 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: 5 E. GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

PROD Size: 5.5 feet: 2877 WITH 525 SX CMT
SURF Size: 8.625 feet: 689 WITH 425 SX CMT

935

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/18/2004 3:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. PUMP 25 SX CMT AT 1700'. PUMP SPACER TO 750'. PUMP CMT TO FILL 5 1/2" FROM 750' TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/18/2004 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 2864'. PUMP 300# HULLS WITH 20 SX CMT. PUMP 25 BBL MUD SPACER TO 1700'. PUMP 25 SX CMT AT 1700'. PUMP 20 BBL SPACER TO 750'. CHECK WITH WIRELINE. PUMP 87 SX CMT TO FILL 5 1/2" FROM TO 750' TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2760	2766		
2742	2745		
2735	2737		
2726	2732		
2714	2722		
2705	2710		

RECEIVED
AUG 30 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
AUG 24 2004
KCC Dodge City

Signed

Jim Holland
(TECHNICIAN)

INVOICED

DATE 8-31-04

INV. NO. 2005060472

Form CP 2/3