

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-05836-00-00
Spot: SESWSW Sec/Twnshp/Rge: 29-19S-9W
330 feet from S Section Line, 4290 feet from E Section Line
Lease Name: F E WALLACE Well #: 4
County: RICE Total Vertical Depth: 3241 feet

Operator License No.: 30364
Op Name: RESOURCE OPERATIONS, INC.
Address: BOX 9487
TULSA, OK 74157

PROD Size: 7 feet: 3200 150 SX CMT
SURF Size: 12.5 feet: 166 150 SX CMT

105³³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/25/2004 3:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY JOE Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP 1700' & 7 sxs common; 1200' & 50 sxs; 850' & 50 sxs; and 250' to 0'.

RECEIVED
KCC DISTRICT #2
AUG 27 2004
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI Witness Type: PARTIAL
Date/Time Plugging Completed: 08/25/2004 7:30 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

CIBP at 1200' and 7 sacks of common cement. Perforated casing at 1200', 850' and 250'. Ran tubing to 1200' and pumped 50 sacks of cement. Pulled to 850' and pumped 50 sacks of cement. Pulled to 250' and pumped cement to surface. Put swedge in casing and pumped cement up the backside.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3216	3216		

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 31 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND #24613

Plugged through: TBG

District: 02

Signed

Jack Luthi

(TECHNICIAN)

INVOICED

Form CP-2/3

8-31-04
2005060476