

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21067-00-00
Spot: NENWNW Sec/Twnshp/Rge: 30-17S-10W
4950 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BECK Well #: 3
County: ELLSWORTH Total Vertical Depth: 3295 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 125 N. MARKET ST. SUITE 1120
WICHITA, KS 67202

PROD Size: 4.5 feet: 3294 75 SX CMT
SURF Size: 8.625 feet: 309 175 SX CMT

\$107⁰⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/19/2004 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Sand to 3250' & 4 sxs; 1350' & 35 sxs; 900' & 35 sxs; 350' - 0'.
Plugging Method:

RECEIVED
KCC DISTRICT #2
AUG 9 - 2004
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI WitnessType: NONE
Date/Time Plugging Completed: 07/20/2004 5:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom to 3250' and 4 sacks of cement. Cut 4-1/2" casing off at 2000'. Pulled to 1350' and pumped 35 sacks of cement. Pulled to 900' and pumped 35 sacks of cement. Pulled to 350' and pumped cement to 0'.

60/40 posmix with 4% gel.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3281 | 3283 | | |

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 31 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED #17809

Plugged through: CSG

District: 02

Signed Jack Luthi
(TECHNICIAN)

INVOICED
DATE 8-31-04
2005060475