

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-00713-00-00
Spot: NESESW Sec/Twnshp/Rge: 33-16S-10W
990 feet from S Section Line, 2970 feet from E Section Line
Lease Name: HORST B Well #: 7
County: ELLSWORTH Total Vertical Depth: 3310 feet

Operator License No.: 32846
Op Name: PREMIER OIL & EXPLORATION INC
Address: 1100 AIRPORT RD
HUTCHINSON, KS 67501

PROD Size: 5.5 feet: 3263
SURF Size: 8.625 feet: 297

\$ 20758

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/16/2004 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY JOE Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Sand bottom 2800' w/ 5 sxs; 1300' w/ 35 sxs; 1000' w/ 35 sxs; 350' w/ 35 sxs.
Plugging Method:

RECEIVED
KCC DISTRICT #2
AUG 18 2004
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/16/2004 5:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Perfs:

Sanded the bottom to 2800' and 5 sacks of common cement. Perforated the casing at 1300', 1000', and 350'.
Ran tubing to 1300' and pumped 35 sacks of cement. Pulled to 1000' and pumped 35 sacks of cement. Pulled to 350' and pumped cement to surface.
Tied to backside and pumped cement to 100 lbs.
60/40 posmix with 4% gel.

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 31 2004
CONSERVATION DIVISION
WICHITA, KS

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 31 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND #24801

Plugged through: TBG

District: 02

Signed

Jack Luthi
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE: 8-31-04
WFO. NO. 2005060473