

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-01829-00-00  
Spot: NENENW Sec/Twnshp/Rge: 13-18S-8W  
4950 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: J A WILLIAMS Well #: 1  
County: RICE Total Vertical Depth: 3258 feet

Operator License No.: 31389  
Op Name: NOBLE PETROLEUM, INC.  
Address: 3101 N. ROCK ROAD, STE 125  
WICHITA, KS 67226

PROD Size: 7 feet: 3151  
SURF Size: 10 feet: 208

6105<sup>89</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/09/2004 2:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

RECEIVED  
KCC DISTRICT #2  
AUG 16 2004  
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/09/2004 5:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded off bottom to 3050' and put 7 sacks of cement on top. Perforated at 900' and 260'. Ran tubing to 900' and pumped 50 sacks of cement. Pulled tubing to 260' and circulated cement to surface.  
  
Pumped 400 lbs cotton hulls at 750' and topped off with 20 sacks of cement after pulling tubing out at 260'. Pumped 35 sacks of cement in 10" with pressure.  
  
60/40 posmix with 4% gel.  
Logtech #3828  
Allied Cement #17677

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3111 | 3258 |      |          |

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 31 2004  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED  
DATE 8-31-04  
2005060421