

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20197-00-00
Spot: NESWNE Sec/Twnshp/Rge: 8-31S-14W
1650 feet from N Section Line, 1650 feet from E Section Line
Lease Name: SKINNER Well #: 1
County: BARBER Total Vertical Depth: 4470 feet

Operator License No.: 3273
Op Name: LOEB, HERMAN L.
Address: PO BOX 524
LAWRENCEVILLE, IL 62439

CIBP Size: feet: 4400 WITH 2 SX CMT
COND Size: 13 feet: 100 WITH 140 SX CMT
PROD Size: 5.5 feet: 4459 WITH 100 SX CMT
SURF Size: 8.625 feet: 785 WITH 485 SX CMT

145²⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/20/2004 4:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4400' WITH 2 SX CMT. PERFORATE AND CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/20/2004 4:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

CASING LEAKS SQUEEZED AT 3570' WITH 100 SX CMT & 2040' WITH 100 SX CMT.
SET CIBP @ 4400' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER.
PERFORATED AT 5 1/2" CASING AT 789'. PUMP DOWN 5 1/2" CASING WITH 225 SX
CMT. CMT DID CIRCULATE UP 5 1/2"/8 5/8" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
4459	4470	OH	
4271	4277		squeezed w/150 sx

RECEIVED
AUG 30 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
AUG 23 2004
KCC Dodge City

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICE

DATE

8-31-04

INV. NO.

2005060468

Form CP-28