

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21739-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 16-19S-10W  
660 feet from N Section Line, 990 feet from W Section Line  
Lease Name: OBERLE Well #: 2  
County: RICE Total Vertical Depth: 3383 feet

Operator License No.: 3208  
Op Name: K & N PETROLEUM, INC.  
Address: 513 W. 6TH ST  
ELLINWOOD, KS 67526

PROD Size: 5.5 feet: 3376 200 SX CMT  
SURF Size: 8.625 feet: 503 350 SX CMT

95  
\$109

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/23/2004 10:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: EDWARD S. NEMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Sanded bottom with 50 sxs of sand & 5 sxs of cement; 35 sxs @ 1250' and 2 sxs of hulls; 35 sxs @ 900' and 200 lbs of hulls; 500' to surface.

RECEIVED  
KCC DISTRICT #2

AUG 4 - 2004

Plugging Proposal Received By: JACK LUTHI WitnessType: NONE  
Date/Time Plugging Completed: 06/23/2004 3:00 PM KCC Agent: JACK LUTHI

WICHITA, KS

Actual Plugging Report:

Sanded bottom with 50 sacks of sand and 5 sacks of cement. Cut 5-1/2" casing off at 1550'. Pulled to 1250' and pumped 35 sacks of cement and 2 sacks of cotton hulls. Pulled to 900' and pumped 35 sacks of cement and 200 lbs of cotton hulls. Pulled to 500' and circulated cement to surface with 130 sacks of cement.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3338	3343		
3178	3180		
3088	3094		
3066	3074		

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 31 2004

Remarks: ALLIED #17915

CONSERVATION DIVISION  
WICHITA, KS

Plugged through: CSG

District: 02

Signed

*Jack Luthi*

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

8-31-04

INV. NO.

2005060466