

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-00471-00-00
Spot: SWNENW Sec/Twnshp/Rge: 8-19S-10W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease Name: STOLTZ Well #: 1
County: RICE Total Vertical Depth: 3334 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S. YALE #609
TULSA, OK 74136

PROD Size: 5.5 feet: 3329 100 SX CMT
SURF Size: 8.625 feet: 237 190 SX CMT

\$108³⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/20/2004 9:00 AM
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 793-2645

RECEIVED
KCC DISTRICT #2
AUG 3 - 2004
WICHITA, KS

Proposed Plugging Method: Sand to 2700' & 35 sxs; 1300' & 35 sxs; 900' & 35 sxs; and 300' to 0'.

Plugging Proposal Received By: JACK LUTHI WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/20/2004 12:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Perforated casing at 1300', 900', and 300'. Ran tubing to 2700'. Pumped 7 sacks of sand and 35 sacks of cement. Pulled tubing to 1300' and pumped 35 sacks of cement. Pulled tubing to 900' and pumped 35 sacks of cement. Pulled tubing to 300' and pumped cement to surface. Cement circulated on both the inside and outside of casing.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3328	3334		

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 3 1 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED #17842

Plugged through: TBG

District: 02

Signed _____

Jack Luthi

(TECHNICIAN)

INVOICED
DATE 8.31.04
2005060461