

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-21293-00-00  
Spot: W2W2SW Sec/Twnshp/Rge: 33-20S-1W  
1250 feet from S Section Line, 330 feet from W Section Line  
Lease Name: OTTE A Well #: 1  
County: MCPHERSON Total Vertical Depth: 3050 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N. MARKET, STE 710  
WICHITA, KS 67202

SURF Size: 8.625 feet: 292 200 SX CMT

8 99.13

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/30/2004 4:30 AM  
Plug Co. License No.: 5892 Plug Co. Name: BERENTZ DRILLING CO., INC.  
Proposal Rcvd. from: ALAN L. DEGOOD Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: Fill hole with heavy mud & spot cement through the drill pipe. Spot 35 sxs. cement on bottom; spot 60 sxs. cement @ 332'; and spot 25 sxs. cement @ 60'. Fill rathole with 15 sxs. cement.

RECEIVED  
KCC DISTRICT #2  
AUG 26 2004

Plugging Proposal Received By: JACK LUTHI WitnessType: NONE WICHITA, KS  
Date/Time Plugging Completed: 06/30/2004 6:30 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Filled hole with heavy mud & spotted cement through the drill pipe. Spotted 35 sxs. cement @ 3,050'; spotted 65 sxs. cement @ 332'; and spotted 25 sxs. cement @ 60'. Filled rathole with 15 sxs. cement.

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 31 2004  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY UNITED CEMENTING & ACID COMPANY, INC. INVOICE #5558.

Plugged through: DP

District: 02

Signed Michael Wilson  
(TECHNICIAN)

INVOICED  
DATE 8-31-04  
INV. NO. 2005060448