

15-121-

19542 0000

3

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: STATE OF KANSAS Fee Fund

Name &amp; FEE FUND

Address

AB oil well

Gas Well

SWD Well/ Input Well

Lease/Well# SEABORN 12

County MIAMI

Well Total Depth 450 feet

Production Pipe: 6 1/4 - 2 Size Feet 450

Surface Casing: 8 Size Feet 20 EST

E14695 D &amp; A

Other well as hereinafter indicated:

Plugging Contractor: K-W OIL WELL SERVICES, INC. Lic. # 3097

Address: 19450 FORD ROAD CHANUTE, KS.66720

Company to plug at: Hour: Day: 11 Month: AUG 2004

Plugging proposal received from: MIKE KEPLEY

Company Name: KEPLEY WELL SERVICE Phone: 620-431-9212

Were: FILL WELL WITH CEMENT FROM TD TO SURFACE.

RECEIVED

AUG 23 2004

KCC WICHITA

Plugging Proposal Received by: FRANK GUILFOYLE

TECHNICIAN

Plugging attended by Agent: All Part X None

Operations Completed: Hour: Day: 13 Month: AUG 2004

Actual Plugging Report: DIG AROUND 2" AND FOUND 6 1/4 AND 8" SURFACE. RUN 1" AND

REAMER TO 425 FT. PULL PIPE. CIRCULATE 20 BBLS. OF WATER AND GOT CIRCULATION AROUND

6 1/4". RUN 1" TO TD AND PUMPED PORTLAND CEMENT TO SURFACE. PULL PIPE AND TOP OFF

WELL. HOOK ONTO 1" AND SQUEEZE CEMENT TO SURFACE ON BACKSIDE OF 6 1/4. PUMP

TOTAL OF 130 SACKS OF CEMENT. WELL PLUGGED.

Remarks: CONTROL NUMBER- 20040020-024 GPS # SEA 24

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Frank Guilfoyle  
TECHNICIAN

pw