

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-00787-00-00  
Spot: SESESE Sec/Twnshp/Rge: 16-17S-8W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: RATHBUN Well #: 2  
County: ELLSWORTH Total Vertical Depth: 3232 feet

Operator License No.: 5088  
Op Name: DARRAH, JOHN JAY, JR.  
Address: 225 NORTH MARKET, STE 300  
WICHITA, KS 67202

PROD Size: 4.5 feet: 3197 125 SX CMT  
SURF Size: 8.625 feet: 282 125 SX CMT

\$105<sup>04</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/21/2004 9:00 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: G P STOEPPELWERTH Company: JOHN JAY DARRAH, JR. Phone: (316) 943-0383

Proposed Plugging Method: 35 sxs bottom; 35 sxs @ 1125'; 35 sxs @ 650'; 330' - 0'.

RECEIVED  
KCC DISTRICT #2  
AUG 3 - 2004

Plugging Proposal Received By: JACK LUTHI WitnessType: PARTIAL WICHITA, KS  
Date/Time Plugging Completed: 07/21/2004 4:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Ran tubing to bottom. Pumped 35 sacks of cement and pulled to 1125'. Perforated pipe with tubing gun. Pumped 35 sacks of cement and pulled to 650'. Perforated pipe again. Pumped 35 sacks of cement and pulled to 330'. Perforated casing. Pumped to surface.

Pumped 100 sacks of cement between 8-5/8" and 4-1/2" casing; circulated to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3197	3232		

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 31 2004  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND CEMENT #24746

Plugged through: TBG

District: 02

Signed

Jack Luthi  
(TECHNICIAN)

INVOICED

DATE 8-31-04

INV. NO. 2005060457