

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02606-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 28-20S-7W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: ENGELLAND Well #: 1
County: RICE Total Vertical Depth: 3344 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY L.L.C.
Address: 1704 LIMESTONE RD.
MCPHERSON, KS 67460

PROD Size: 5.5 feet: 3330 125 SX CMT
SURF Size: 8.625 feet: 307 150 SX CMT

\$ 108⁶⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/24/2004 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Sand to 3280' & 5 sxs; 1050' & 35 sxs; 600' & 35 sxs; and 357' to 0'.
Plugging Method:

RECEIVED
KCC DISTRICT #2
AUG 27 2004
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/24/2004 1:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom to 3280' and 5 sacks of common cement. Cut casing off at 1409'. Pulled to 1050' and pumped 35 sacks of cement with 200 lbs of cotton hulls. Pulled to 600' and pumped 35 sacks of cement. Pulled to 357' and circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3330	3344		

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 31 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED #20077

Plugged through: CSG

District: 02

Signed Jack Luthi
(TECHNICIAN)

INVOICED

DATE 8.31.04

INV. NO. 2005060454