

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21995-00-01  
Spot: NENW Sec/Twnshp/Rge: 16-6S-22W  
540 feet from N Section Line, 2050 feet from W Section Line  
Lease Name: KEISWETTER Well #: 1  
County: GRAHAM Total Vertical Depth: 3920 feet

Operator License No.: 6484  
Op Name: ANDERSON ENERGY, INC.  
Address: 221 S. BROADWAY, SUITE 302  
WICHITA, KS 67202

PROD Size: 4.5 feet: 3921 675 SX  
SURF Size: 8.625 feet: 260 180 SX

8/27/04

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/10/2004 8:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: GARY WAGNER Company: SWIFT SERVICES, INC. Phone: (785) 735-4412

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
PBTD 3825'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/10/2004 11:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing to 3600' - spotted 75 sxs cement with 300# hulls.  
Pulled tubing to 2400' - spotted 50 sxs cement with 100# hulls.  
Pulled tubing to 1200' - spotted 50 sxs cement to circulate at surface.  
POOH with tubing and squeezed casing with an additional 25 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.  
Rigged up to 8 5/8" casing and pressured up to 500# - no cement pumped.

Perfs:

Top	Bot	Thru	Comments
3830	3832		
3744	3750		
3731	3734		
3592	3596		
3520	3523		

RECEIVED  
AUG 31 2004  
KCC WICHITA

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 31 2004  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel  
(TECHNICIAN)

INVOICED

DATE 8.31.04

2005060449

Form CP-2/3

AUG 26 2004

STATE: KANSAS COUNTY: GRAHAM OWWO 16-6S-22W  
FIELD: SPRINGBIRD W2 NE NW  
OPER: ANDERSON ENERGY 540 FNL 2050 FWL SEC  
WELL: 1 KEISWETTER ELEV: 2361 KB  
API: 15-065-21995-0001 STATUS: OIL-WO 2356 GR  
SPUD: 08/13/92 COMP: 08/18/92  
DTD: 3920 LTD: FTD: OREAD PBTD: 3560

LOC:

IP: COMP 8/18/92, IPP 55 BO, 30 BWPD, GTY 28 **PROD ZONE-** OREAD 3520-3523  
NO CORES OR DSTS FIRST REPORT & COMPLETION

TBG: 2 3/8 @ 3542; DRLG COMP 08/14/92  
OWWO: OWWO: OLD INFO: FORMERLY ENERGY PROD 1 KEISWETTER. ELEV: 2356 GR,  
2361 KB. SPUD 6/12/84. 8 5/8 @ 260 W/180 SX, 4 1/2 @ 3921 W/225 SX. LOG TOPS:  
STONE CORRAL 2013-2044, TOPEKA 3352, HEEBNER 3548-3552, TORONTO  
3574-3585, LANSING-KANSAS CITY 3591-3781. OTD 3920. COMP 7/5/84. IPS 100  
BOPD, GTY 37. PROD ZONE: LANSING 3592-3750.

PERFS: PERF (LANSING H) 3710-3712 W/4 PF, ACID W/1250 GALS, 15% NE, CIBP @ 3560  
TSTG RESULTS NOT RPTD

PRODUCING INTERVAL: PERF (OREAD) 3520-3523 W/4 PF, ACID W/750 GALS, 15% NE,

OPER ADD: 200 E FIRST ST STE 414, WICHITA, KS, 67202 PHONE (316) 265-7929;  
CONTR: EXPRESS WELL SRVC

(OVER)

COPYRIGHT 1994 PETROLEUM INFORMATION CORPORATION

DATE 01/07/94 CARD #00002-KS

STATE: KANSAS COUNTY: GRAHAM OWWO 16-6S-22W  
FIELD: SPRINGBIRD W2 NE NW  
OPER: ANDERSON ENERGY 540 FNL 2050 FWL SEC  
WELL: 1 KEISWETTER ELEV: 2361 KB  
(CONTINUED) STATUS: OIL-WO 2356 GR  
COMP: 08/18/92

GEOL: ROGER WELTY

COPYRIGHT 1994 PETROLEUM INFORMATION CORPORATION

DATE 01/07/94 CARD #00002-KS