

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22145-00-00  
Spot: W2SENW Sec/Twnshp/Rge: 16-6S-22W  
3300 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: KEISWETTER Well #: 2  
County: GRAHAM Total Vertical Depth: 3860 feet

Operator License No.: 6484  
Op Name: ANDERSON ENERGY, INC.  
Address: 221 S. BROADWAY, SUITE 302  
WICHITA, KS 67202

PROD Size: 4.5 feet: 3859 600 SX  
SURF Size: 8.625 feet: 255 190 SX

\$ 125<sup>45</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/09/2004 8:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: GARY WAGNER Company: SWIFT SERVICES, INC. Phone: (785) 735-4412

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/09/2004 1:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementers to 4 1/2" casing - squeezed 225 sxs 60/40 pozmix - 10% gel with 500# hulls.  
Max. P.S.I. 1900#. S.I.P. 500#.  
Rigged up cementers to 8 5/8" - pressured up to 500# - no cement pumped.

Perfs:

Top	Bot	Thru	Comments
3782	3785		

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 31 2004  
CONSERVATION DIVISION  
WICHITA, KS

RECEIVED  
AUG 31 2004  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

DATE

8-31-04

INV. NO

2005060449

Form CP-2/3

AUG 26 2004

ENERGY PRODUCTION, INC.

1100 BITTING BLDG.

WICHITA, KS 67202

CONTR

ABERCROMBLE DRILLING

CTY

GRAHAM

16-6-22W

C W/2 SE NW

GEOL

ROGER WELTY

FIELD

SPRINGBIRD EXT  
(1/8 S)

ELV

2395 KB SPD 3/21/85

CARD  
ISSUED

7/4/85


IP

P 30. BOPD

2390 GL

DRLG COMP 3/30/85

LKC 3782-3785



LOG	Tops	Depth/Datum
ANH	.....	2044 + 351
TOP	.....	3408-1013
HEEB	.....	3800-1205
TOR	.....	3623-1228
LKC	.....	3641-1246
LTD	.....	3859-1464
RTD	.....	3860-1465

API 15-065-22, 145

8 5/8 " 255 / 190SX, 4 1/2 " 3859 / 150SX, 4 1/2 " 1450 / 450SX, TWO STAGE AT 1450 / 450SX

DST (1) 3595-3650 (SHAW) / 30-30-30-30, REC 40' M, SIP 1031-997#, FP 57-57 / 69-69#, HP 1840-1818#, BHT 100"

DST (2) 3775-92 (LKC) / 30-45-60-90, 270' GIP, REC 120' CL OIL, 30' OCM, SIP 264-264#, FP 34-46 / 69-92#, HP 1954-1931#, BHT 103"

DST (3) 3818-60 (LKC) / 45-45-45-45, REC 40' SOCM, SIP 1112-1021#, FP 44-44 / 55-55#, HP 2023-2000#, BHT 112"

MICT - CO, PF (LKC) 3782-85, W / 2 SPF, AC 500G (15% INS) & 1500G (20% STABILIZED GEL), SWB DWN, SO, SET 2 3/8 " TBG AT 3803', POP, P 30 BOPD, NW (GR 39°), 5/17/85

COPYRIGHT 1984  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS