

4-4

348
00-00R

6 031525

API NUMBER 15- 039-20,872

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE SW, SEC. 26, T 3, S, R 29 W/E^x

2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4868

Lease Name Sauvage Well # 1
County Decatur 135.20

Operator: Asher Associates, Inc.
Name & Address: 7340 E. Caley Avenue #310
Engelwood, Colorado 80202

Well Total Depth 4160 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Golden Eagle Drilling Inc. License Number 8682
Address McCook Nebraska

Company to plug at: Hour: _____ PM Day: 4 Month: April Year: 19 91

Plugging proposal received from Dave Paschall

(company name) Golden Eagle (phone) _____

were: 8 5/8 set at 266 w/175 sks cwc. Circ. hole w/no lesws than 35 vis mud

w/no loss or gain of fluids. Keep hole full and balance plugs w/mud.

Order 200 sks 60/40 poz 6% gel 8 5/8 w.p. Halliburton Cement Co.

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1991

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Carl Goodrow (TECHNICIAN) 4-25-91

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 6:00 PM Day: 4 Month: April Year: 19 91

ACTUAL PLUGGING REPORT Spot plugs w/drill pipe at 2600 w/25 sks

1780 w/100 sks and hulls

315 w/40 sks

40 w/10 sks

Circ 15 sks in rathole

Circ 10 sks in mousehole.

Remarks: _____

INVOICED

(If additional description is necessary, use BACK of this form.)

(did not) observe this plugging.

DATE 5-7-91

INV. NO. 31762

Handwritten initials

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow