

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-039-20,721-00-00

SW¹/₄, Sec. 11, T 3 S, R 29 W¹/₂

660 feet from N/X section line

450 feet from W/X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6962

Lease Name Sauvage Well # 11-12

Operator: Sauvage Drilling Inc.
Name & Oberlin, Kansas 67749
Address

County Decatur

Well Total Depth 3830 feet 126.47

Conductor Pipe: Size feet

Surface Casing: Size 8⁵/₈ feet 229 CWC 190

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie License Number 5422

Address 801 Union Center, Wichita, Kansas 67202

Company to plug at: Hour: 9 Day: 10 Month: February Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO

(company name) (phone)

were: Order 195 sks 50/50 poz mix 6% gel 3% cc 8⁵/₈ plug. Jett pitts circulate
hole with heavy mud displace 25 sks cement thru drill pipe at 2350 - heavy mud to
1650' and 100 sks cement thru drill pipe heavy mud to 240' and 40 sks cement thru drill
pipe, heavy mud to 40 sks cmt, plug 1/2 sk hulls and 10 sks cement - cementing to base
of cellar. 10 sks in Rat Hole 10 sks. in Mouse Hole

Signed Gilbert P. Lerka
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:45 P.M. Day: 10 Month: February Year: 1984

ACTUAL PLUGGING REPORT

1st plug @ 2350 w/25 sks.

2nd plug @ 1650 w/100 sks.

3rd plug @ 240 w/40 sks.

4th plug @ 40 w/10 sks.

10 sks. in Rat Hole. 10 sks. in Mouse Hole

Remarks:

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1984

CONSERVATION DIVISION
Wichita, Kansas

2-21-84

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed Gilbert P. Lerka
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 2-23-84

INV. NO. 0357