

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-039-20,808 -0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Boundry Petroleum, Inc. OPERATORS LICENSE NO. 3271
ADDRESS 350 Interlocken Parkway, #250, Broomfield, CO 80020 PHONE # (303) 460-1550
LEASE (FARM) Chaffin WELL NO. 1-20 WELL LOCATION NW NE SW COUNTY Decatur
SEC. 20 TWP. 3S RGE. 28 (~~Box~~) (W) TOTAL DEPTH 3980 PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 8-5/8 SET AT 265 CEMENTED WITH 175 SACKS
CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
PERFORATED AT _____

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug 2450'-25 sacks; 2nd plug 1650'-100 sacks and
1 sack flocel; 3rd plug 300'-40 sacks; 4th plug 40' to solid bridge-10 sacks; rathole-15sacks; all cement 60/40
posmix, 6% gel, 3% ca. cl.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? no IS ACO-1 FILED? no
(If not, explain) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 3-6-87 9:00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Harold Maley PHONE # (913) 674-5768

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 801 Union Center, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack K. Whatton 03-11-1987
MAR 11 1987
(Operator or Agent)
Jack K. Whatton, Secy/Treas.

DATE: 3-10-87