

1/13/98  
81

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-039-20,906-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Pickrell Drilling Company, Inc. KCC LICENSE # 5123  
(owner/company name) (operator's)  
ADDRESS 110 N. Market, Suite 205 CITY Wichita,

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-8427

LEASE Lund "B" WELL# 1 SEC. 13 T. 3S R. 28 (East/West)

C - NW - SW SPOT LOCATION/QQQQ COUNTY Decatur

1980 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM E/(W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 229'KB CEMENTED WITH 165sx SACKS

PRODUCTION CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: N/A

ELEVATION 2719' / 2724' T.D. 4000' PBDT \_\_\_\_\_ ANHYDRITE DEPTH 2470(+254)  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING P&A as follows: 25sx @ 2445', 100sx @ 1580', 40sx @ 279', 10sx @ 40', 15sx in RH (total 190sx) of 60-40 poz, 6% gel w/1/4# FS/sx. Completed @ 2:30 PM on 12-13-97.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Michael Kerns PHONE# (316) 793-5742

ADDRESS P.O. Box 1303 City/State Great Bend, Kansas 67530

PLUGGING CONTRACTOR Pickrell Drilling Co. Inc. KCC LICENSE # 5123

ADDRESS 110 N. Market, Suite 205 - Wichita, KS. PHONE # (316) 262-8427  
(company name) (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Completed @ 2:30 PM on 12-13-97.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1-9-98 AUTHORIZED OPERATOR/AGENT: \_\_\_\_\_

(signature)  
C. W. Sebts

RECEIVED  
01-12-1998  
JAN 12 1998