


15-153-00048-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

RAWLINS CO., KANS. County. Sec. 10 Twp. 3S Rge. 32W (E) (W)

Location as "NE/CNW/SW" or footage from lines **SE SE SE**  
Lease Owner **LEE PHILLIPS OIL COMPANY**  
Lease Name **BASTIAN** Well No. **1**  
Office Address **1407 Union National Building, Wichita, Kans.**  
Character of Well (completed as Oil, Gas or Dry Hole) **Dry Hole**  
Date well completed **11-2-59** 19\_\_\_\_  
Application for plugging filed **11-2-59** 19\_\_\_\_  
Application for plugging approved **11-2-59** 19\_\_\_\_  
Plugging commenced **11-2-59** 19\_\_\_\_  
Plugging completed **11-2-59** 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? **yes**

Name of Conservation Agent who supervised plugging of this well **A. D. Fabricius**  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well **4634'** Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS						CASING RECORD
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	341'	---

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fill with heavy mud to 550' set plug with 20 sx cement thru drill pipe. Fill with heavy mud set plug at 325' with 20 sx cement thru drill pipe. Fill with heavy mud to 40' set solid bridge with 10 sx cement to base of cellar.  
Job complete 11-2-59

**RECEIVED**  
STATE CORPORATION COMMISSION  
NOV 12 1959  
11-12-1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor **K & E DRILLING, INC.**  
Address **719 Union Center, Wichita 2, Kansas**

STATE OF **KANSAS**, COUNTY OF **SEDGWICK**, ss.  
**DALE STILCOTT** (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Dale Stilcott*  
**DALE STILCOTT, of K & E DRILLING, INC.**  
**719 Union Center, Wichita 2, Kansas**  
(Address)

SUBSCRIBED AND SWORN TO before me this **10th** day of **November**, 19**59**

My commission expires **August 11th, 1962.**

*Patricia M. Edwards*  
**Patricia M. Edwards,** Notary Public.



15-153-00048-00-00

# DRILLER'S WELL LOG

OPERATOR: LEE PHILLIPS OIL COMPANY  
1407 Union National Bldg  
Wichita, Kansas

WELL NAME: #1 BASTIAN

LOCATION: SE SE SE, Sec 10-38-32W  
RAWLINS COUNTY, KANSAS

CONTRACTOR: K&E DRILLING, INC.  
719 UNION CENTER BLDG.  
WICHITA, KANSAS

COMMENCED: October 22nd, 1959

CASING RECORD: 8-5/8" @ 341' (300 SK CMT)

COMPLETED: November 2nd, 1959

ELEVATION: 2977' KB

ROTARY TOTAL DEPTH: 4634'

PRODUCTION: D & A

## FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Soil & Clay	95
Sand & Gravel	155
Sale & Shells	341
Shale	1790
Sand & Shale	2050
Sand	2170
Shale & Lime	2345
Shale & Sand	2450
Anhydrite	2470
Lime & Shale	2530
Shale	2560
Limey Anhydrite	2590
Shale & Lime	2755
Lime & Shale	3435
Lime	3615
Lime & Shale	2735
Lime	4255
Lime & Shale	4530
Lime	4541
Mississippian	4575
Chert & Lime	4620
Cherty Lime	4634
Arbuckle Lime	4635'
R.T.D.	4655

RECEIVED  
STATE COMMISSION  
NOV 12 1959  
CONSERVATION DIVISION  
Wichita, Kansas

## CERTIFICATION

State of KANSAS  
County of SEDGWICK { ss:

I, Dale Silcott, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

*Dale Silcott*

Subscribed and sworn to before me this 10th day of November, 19 59.

*Patricia M. Edwards*

My Commission expires: August 11th, 1962. Patricia M. Edwards, Notary Public.

