

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.
Address: 250 N. Water, Suite 300
Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 7/19/04 (Date)
by: Darrell Dipman w/ KCC in Hays, KS (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
4048-52,4066-68,4084-86,4094-96 Depth to Top: _____ Bottom: _____ T.D. _____
4117-19,4149-52,4149-53,4197-4201 Depth to Top: _____ Bottom: _____ T.D. _____
4215-17,4236-40 Depth to Top: _____ Bottom: _____ T.D. _____

15-153-20084-00-00
API Number: 15-10/6/70
Lease Name: Canoj B (Kisling #1 RJP KCC)
Well Number: #3-1
Spot Location (QQQQ): C - NW - NE -
4620 Feet from North / South Section Line
1980 Feet from East / West Section Line
Sec. 10 Twp. 1 S. R. 34 East West
County: Rawlins
Date Well Completed: 10/6/70
Plugging Commenced: 7/19/04
Plugging Completed: 7/19/04

RECEIVED
AUG 20 2004
KCC WICHITA

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	<u>370 364</u>	8 5/8	<u>370 364</u>	0
	Production	Surface	4364	5 1/2	4364	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

7/19 Dug pit. TIH w/tbg to 2470'. CIBP @ 3900'. RU Swift. Pumped 70 sxs SMD & 300# hulls. No circ. Pulled tbg to 1200'. Pumped 70 sxs SMD & 400# hulls. Little circ. Pulled tbg to 600'. Pumped 65 sxs SMD & 200# hulls & circ cmt to surface. TOH w/tbg. Pump 30 sxs SMD down 5 1/2" csg. Not full. Hooked up to 8 5/8". Pumped 20 sxs & press to 200# & held. SI. Pumped 30 sxs down 5 1/2", not full. Let sit 1/2 hr. Top off w/10 sxs & csg stayed full. Job completed @ 2:30 PM. Witnessed & approved by Darrell Dipman w/KCC in Hays, KS. Total 295 sxs & 900# hulls.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606
Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.
State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 250 N. Water, Suite 300; Wichita, KS 67202



SUBSCRIBED and SWORN TO before me this 19th day of August, 20 04
Kristin Grady My Commission Expires: 2/06/08
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

SWIFT SERVICES, INC.

PO BOX 466

NESS CITY, 67560-0466

Invoice

DATE	INVOICE #
7/19/04	7017

BILL TO
Murfin Drilling Co Inc

USED FOR PIA 36 Cement

APPROVED Jy ✓

Cahoj B-3-1

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Operator	Job Purpose
Net 30	3-1	Cahoj	Rawlins	Co Tools	Oil	Abandoned	Wayne	PTA

PRICE REFERENCE...	DESCRIPTION	QTY	UNIT PRICE	AMOUNT
575W	Milage	150	2.50	375.00T
576W-P	Pump Charge	1	550.00	550.00T
275	Cotton Seed Hulls	9	20.00	180.00T
330	Swift Multi-Density	295	10.00	2,950.00T
581W	Service Charge Cement	325	1.00	325.00T
583W	Drayage	2,417.25	0.85	2,054.66T
	Subtotal			6,434.66
	Sales Tax		5.30%	341.04

RECEIVED
AUG 20 2004
KCC WICHITA

Thank you for your business.	Total	\$6,775.70
------------------------------	--------------	------------



CHARGE TO:
 ADDRESS: MURPHY DRUG CO.
 CITY, STATE, ZIP CODE:

TICKET No 7017

PAGE 1 OF 1

SERVICE LOCATIONS 1. <u>NESS CITY, KS</u>	WELL/PROJECT NO. <u>3-1</u>	LEASE <u>CAHOJ "B"</u>	COUNTY/PARISH <u>RAWLINS</u>	STATE <u>KS</u>	CITY	DATE <u>7-19-04</u>	OWNER <u>SAME</u>
2.	TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR <u>Co Tools</u>	RIG NAME/NO.	SHIPPED VIA <u>CT</u>	DELIVERED TO <u>LOCATED</u>	ORDER NO.	
3.	WELL TYPE <u>OIL</u>	WELL CATEGORY <u>ABANDONED</u>	JOB PURPOSE <u>PTA</u>	WELL PERMIT NO.	WELL LOCATION <u>ATWOOD - 2nd ST W, 3rd, 1st, 1/2 W, S</u>		
4. REFERRAL LOCATION	INVOICE INSTRUCTIONS						

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575		1			MILEAGE # 106	150		MC		2.50	375.00
576		1			PUMP SERVICE	1		JOB		550.00	550.00
275		1			CORROJ SEA NUTS	9	900	SKS	LBS	20.00	180.00
330		1			SWIFT MULTI-DRAW ST-4425	295		SKS		10.00	2950.00
581		1			SERVICE CHARGE CUMINT	325		SKS		1.00	325.00
583		1			DEBRAGC	32230	2417.25	LBS	TM	.85	2054.66

RECEIVED
 AUG 20 2004
 KCC WICHITA

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X [Signature]
 DATE SIGNED 7-19-04 TIME SIGNED 1215
 A.M.
 P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	6434.66
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?					
WE UNDERSTOOD AND MET YOUR NEEDS?					
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX	341.04
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL	6775.70
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND					

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR Wade Wilson APPROVAL

Thank You!

JOB LOG

SWIFT Services, Inc.

DATE 7-19-04 PAGE NO. 1

CUSTOMER MURPHY DRUG Co. WELL NO. 3-1 LEASE CAHOJ "B" JOB TYPE PTA TICKET NO. 7017

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL/GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1145							ON LOCATION
								2 3/8 x 5 1/2 CSDP = 3900' PRES = 4048-4240 HOLES = 1140-1265 1265-2621 BAD DPL = 1600'
	1215	5	33	✓		250		1ST PLUG = TUBING = 2470' 70 SKS CNT = 300 HALL
	1300	5	33	✓		400		2ND PLUG = TUBING = 1200' 70 SKS CNT = 400 HALL (24 BBL CORRECTION)
	1330	4 1/2	31	✓		350		3RD PLUG = TUBING = 600' 65 SKS CNT = 200 HALL CNT TO SURFACE
								PULL TUBING AT WELL
	1400		14	✓				PUMP 30 SKS CNT DOWN 5 1/2" CSG - NOT FULL
	1420	2 1/2	10	✓		200		PUMP 20 SKS CNT DOWN BRANCH HEAD 200 SHUT IN
	1425		14	✓				PUMP 30 SKS CNT DOWN 5 1/2" CSG - SLOW DROP (WAIT 20 MINUTES)
	1500		5					TOP OFF 10 SKS CNT
								WASH UP
	1530							JOB COMPLETE

RECEIVED
AUG 20 2004
KCC WICHITA

THANK YOU
WALK, NICK, SUNE