

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189-20669-00-00

LEASE NAME Kinney Chester Sand Unit

WELL NUMBER 602

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1980 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 25 TWP. 34 RGE. 35 (S) or (W)

COUNTY Stevens

Date Well Completed 12-8-83

Plugging Commenced 8-4-04

Plugging Completed 8-5-04

LEASE OPERATOR Oxy USA, Inc

ADDRESS Box 2528 Liberal, KS

PHONE (620) 629 4200 OPERATORS LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-17-04 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Chester Depth to Top 6503 Bottom 6515 T.D. 6750

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD RECEIVED

Formation	Content	From	To	Size	Put in	Pulled out
				8 3/8	1641	
				5 1/2	6760	2333

AUG 30 2004  
KCC WICHITA

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set  
CIBP + 2 5x cmt. 5675 to 5655 Shot & pulled 5 1/2 to 1700. Circ. hole w/mud 50 3x 1700 to 1550 Circ. hole w/mud 30 3x 600 to 500  
10 3x 40-0 Cut off & capped 8 3/8 3' ft. below Gil.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc. PO Box 2528 Liberal, KS 67905

STATE OF Kansas COUNTY OF Seward, ss.


Kenny Andrews (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) [Signature]

(Address) PO Box 2528 Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 26th day of Aug, 1<sup>st</sup> 2004

[Signature]  
Notary Public



Expires: Oct 1, 2005



OXY USA Inc.

1701 N. Kansas, Liberal, KS 67901  
P.O. Box 2528, Liberal, KS 67905-2528

August 25, 2004

Kansas Corporation Commission  
Wichita State Office Bldg.  
130 South Market, Room 2078  
Wichita, Kansas 67202

RECEIVED  
AUG 30 2004  
KCC WICHITA

Re: OXY USA INC.  
Well Plugging Record ( CP-4 )  
Closure of Surface Pond ( CDP-4 )  
Kinney Chester Sand Unit # 602  
API # 15-189-20669  
Section 25-34S-35W  
Stevens Co, KS.

To Whom It May Concern:

Please find enclosed the Well Plugging Record (CP-4 ) for the subject well. Also, please find the pit closure form ( CDP-4 ) Thanks for your help.

If there are any questions or you require further information, please contact me at the above address or by Phone at ( 620 ) 629 - 4232.

Sincerely,

Kenny L. Andrews  
Engineering Technician  
Liberal, Kansas