

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Decatur

County. Sec. 16 Twp. 38 Rge. 29 (X) (W)

Location as "NE/CNW&SW&" or footage from lines NW NE NE

Lease Owner Sauvage Drilling Co., Inc.

Lease Name Tilden Well No. 1

Office Address Oberlin, Kansas.

Character of Well (completed as ~~Oil~~ Gas or Dry Hole)

Date well completed 6-4-65 19 65

Application for plugging filed 6-14 19 65

Application for plugging approved 6-14 19 65


Plugging commenced 6-14 19 65

Plugging completed 6-14 19 65

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Bill Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4158 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled bottom hole with heavy mud and set plug 1/2 sax hulls & 20 sax cement 700'
off bottom - filled with heavy mud to 240' set plug 1/2 sax hulls & 20 sax cement
filled hole with heavy mud & set plug & filled top with 10 sax cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 28 1965

6-28-65

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sauvage Drilling Co., Inc

Address Oberlin, Kansas.

STATE OF Kansas, COUNTY OF Decatur, ss.

W. W. Sauvage (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Sauvage

(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of June, 1965

My commission expires June 25, 1968

Notary Public.



Operator ----- Sauvage Drilling Co., Inc.
Oberlin, Kansas.

Location- NW NE NE 16-3-29W
Decatur County, Kansas.

Farm Name..... Tilden
Well No. 1
Contractor..... Company Tools
Rotary Commenced.... 5-22-65
Rotary Completed.... 6-4-65

Casing Record
125 Feet of 8 5/8"
Surface Casing

15-039-30003-0000

Figures Denote Bottom of Formation

Shale-----626'
Shale & clay-----1130'
Shale-----1310'
Sand-----1495'
Sand & Shale-----2000'
Shale-----2204'
Gyp-----2223'
Shale-----2230'
Shale & Gyp-----2500'
Shale & Shells-----2595'
Shale-----2720'
Lime-----2794'
Lime & Shale-----2960'
Shale & Shells-----3045'
Lime-----3119'
Lime & Shale-----4158' TD

RECEIVED
STATE CORPORATION COMMISSION

JUN 28 1965

6-28-65

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas)
) SS
Decatur County)

I hereby certify that the foregoing is, to the best of my knowledge and belief, a true and correct drilling log as shown by the drilling reports in connection with the aforesaid well.

W. S. Sauvage
W. S. Sauvage

Subscribes and sworn to before me, the undersigned, a Notary Public, this 25 of June, 1965

Hubert A. Jensen

My commission expires June 25, 1968