

15-153-01001-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rawlins County. Sec. 18 Twp. 3 Rge. 35 (E) (W)
Location as "NE/CNW/SW" or footage from lines C - SW - SW
Lease Owner Empire Drilling Co.
Lease Name Beeson Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced Nov. 13 1963
Plugging completed Nov. 13 1963
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4768 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4768 feet to surface feet for each plug set.
Sanded up to 4200' dump 5 sacks of cement on bottom. Pulled pipe to 720' Cic. with mud, pump 20 sacks of cement to 630' pulled pipe to 300' pump 20 sacks of cement to 300' pulled pipe, put 10 sacks on top. Well completed.

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1963

CONSERVATION DIVISION
Wichita, Kansas

11-27-63

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.
Address P.O. Box 313 Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dan J. Kornfeld

(Employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
650-4th National Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of November, 19 63

My commission expires October 21, 1966

[Signature]
Lucille H. Harr
Notary Public.

LOG

15-153-01001-00-00

COMPANY: Empire Drilling Company
 CONTRACTOR: Empire Drilling Company
 FARM: Beeson #1
 LOCATION: C SW SW Section 18-3S-35W, Rawlins County, Kansas
 COMMENCED: August 31, 1962 ELEVATION: 3293 KB
 COMPLETED: September 15, 1962 POTENTIAL: Producer

0	to	100	Surface - Shale
100	to	1915	Sand & Shale
1915	to	2215	Shale
2215	to	2425	Shale & Gyp
2425	to	2680	Sand Stone & Shale
2680	to	2780	Shale & Shells with Gyp
2780	to	2920	Shale & Shells
2920	to	3080	Shale Redbed
3081	to	3127	Anhydrite
3127	to	3355	Shale
3355	to	3544	Lime & Shale
3544	to	3650	Shale
3650	to	3750	Lime & Shale
3750	to	3802	Lime
3802	to	4092	Lime & Shale
4092	to	4130	Lime
4130	to	4220	Lime & Shale
4220	to	4282	Lime
4282	to	4370	Lime & Shale
4370	to	4440	Lime
4440	to	4660	Shale & Lime
4660	to	4671	Lime
4671	to	4710	Lime & Shale
4710	to	4755	Shale & Hard Sand
4755	to	4875	Sand & Shale
4875	to	4890	Mississippi
4890			Rotary Total Depth

SET: 309' of 8 5/8" with 150 sacks cement,
 150 joints of 5 1/2" with 150 sacks at 4768'

SCHLUMBERGER LOG TOPS:

Topeka	4017'	-724
Deer Creek	4058'	-765
Oread	4124'	-831
Heebner	4162'	-869
Douglas Sand	4177'	-884
Lansing	4209'	-916
Zone 2A	4262'	-969
Zone 5	4315'	-1022
Zone 6	4358'	-1065
Zone 6A	4375'	-1082
Zone 7	4404'	-1111
Zone 8	4438'	-1145
Base Kansas City	4473'	-1180
Cherokee Group	4684'	-1391
Mississippian	4852'	-1559
Log Total Depth	4891'	

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1963
11-27-63
CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Beeson #1, C SW SW Section 18-3S-35W, Rawlins County, Kansas, as reflected by the files of Empire Drilling Company.

Dan J. Kornfeld
 Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 24th day of September, 1962.

Lucille H. Harr
 Lucille H. Harr, Notary Public

My commission expires October 21, 1962.