

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15-145-00892-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 3/10/54

Well Operator: QUALITY WELL SERVICE (Owner / Company Name) KCC License #: 31925 (Operator's)

Address: 401 W MAIN City: LYONS

State: KS Zip Code: 67554 Contact Phone: (620) 727 - 3410

Lease: O. E. SMITH Well #: A-1 Sec. 28 Twp. 22 S. R. 15  East  West

NE - SE - NE Spot Location / QQQQ County: PAWNEE

1650 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 10 3/4 Set at: 206 Cemented with: 200 Sacks

Production Casing Size: 7 Set at: 3989 Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3980-87 ARBUCKLE 3962-50 DOUGLAS

Elevation: 1998 ( G.L. /  K.B.) T.D.: 3992 PBDT: 3970 Anhydrite Depth: 950  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): AS KCC REQUIRES

RECEIVED

AUG 30 2004

KCC WICHITA

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: JOE MAES

Phone: (620) 727 - 3410

Address: 602 S CLARK City / State: LYONS KS 67554

Plugging Contractor: QUALITY WELL SERVICE (Company Name) KCC License #: 31925 (Contractor's)

Address: 401 W MAIN LYONS KS 67554 Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8/20/04 Authorized Operator / Agent: Joe Maes (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Please return to

NATURAL GAS AND OIL CORPORATION  
1009 Central Building  
WICHITA 2, KANSAS

**PHILLER'S LOG**

**COMPANY:** Natural Gas and Oil Corporation and  
Cities Service Oil Company

**CONTRACTOR:** Drilling Department of  
Natural Gas and Oil Corporation

**WELL:** O. E. Smith "A"-1, NE SE NE Sec 28-22N-15W  
Pawnee County, Kansas

**COMMENCED:** March 10, 1954 - Rotary  
March 31, 1954 - Cardwell

**COMPLETED:** March 24, 1954 - Rotary  
April 3, 1954 - Cardwell

*Pot. 240 Bopd  
& No. wt  
Gravity 38.0*

**ELEVATION:** 1998 MB

0	to	80	Sand
80	to	120	Sand and clay
120	to	350	Shale and shells
350	to	475	Sand
475	to	950	Red bed and shale
950	to	980	Anhydrite
980	to	1675	Shale and shells
1675	to	3415	Lime and shale
3415	to	3419	Shale
3419	to	3495	Lime and shale
3495	to	3531	Shale
3531	to	3541	Lime and shale
3541	to	3770	Lime
3770	to	3935	Lime and shale
3935	to	3955	Shale
3955	to	3966	Sand
3966	to	3980	Shale
3980	to	3990	Arbuckle
		3990	T. D. Rotary
		3992-	T. D. Cardwell

Set 206 feet of 10 3/4" 32# surface pipe. Cemented with 200 sacks cement and 4 sacks calcium chloride.

Set 7 casing at 3969. Cemented with 150 sacks cement.

<b>TOPS:</b>	Anhydrite	950	Lansing	3541	Viola	3581
	Hechner	3415	Base KC	3775	Simpson	3936
	Brown Ls	3531	Conglomerate	3846 @ 34		3954
					Arbuckle	3980

**DRILL STEM TESTS:**

- #1- 3543-55, open 1 hr, weak 3 min blow, rec 15' mud, SI 20 min, 1200# BHP. 0# IFF and 0# FFP.
- #2- 3956-66, open 1 hr, weak steady blow, rec 120' gas, 65' heavily oil cut mud, SI 30 min, 0# IFF and FFP, 1250# BHP.
- #3- 3980-90, open 1 hr, strong blow, rec 240' gas in pipe, 3240' clean gassy oil, 60' oil and gas cut mud, SI 15 min, IFF 210#, FFP 1100#, no BHP, clock stopped.

Run Schlumberger

Drilled plug and made 2 feet new hole. Hole filled up 2500 feet oil in 5 hours, no water. Set overnight filled up 3600 feet oil, no water. Swabbed 20 BOPM for 2 hours.

April 26, 1954, State Potential 240 BOPD, no water, 38.0 Grav.

RECEIVED  
AUG 30 2004  
KCC WICHITA

**C E R T I F I C A T E**

I, Claud Sheets, do hereby certify that the above and foregoing is a true and correct copy of the log of the O. E. Smith "A" #1, NW SW NE Section 26-22N-15W, Pawnee County, Kansas, as reflected by files of the Natural Gas and Oil Corporation.

*Claud Sheets*

Claud Sheets, Regional Geologist

Subscribed and sworn to before me, a Notary Public, within and for Sedgewick County, Kansas this 30th day of April, 1954.

*Esther Russell*

Esther Russell, Notary Public

My commission expires May 25, 1957.

RECEIVED  
AUG 30 2004  
KCC WICHITA

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Quality Well Service, Inc.  
401 West Main  
Lyons, KS 67554

August 31, 2004

Re: O E SMITH A #1  
API 15-145-00892-00-00  
NESENE 28-22S-15W, 1650 FNL 330 FEL  
PAWNEE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

Sincerely  
  
David P. Williams  
Production Supervisor