

15-153-00009-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM
File One Copy

Lease Owner Natural Gas & Oil Corp Address 1009 Central Building, Wichita, Ks
(Applicant)

Lease (Farm Name) W. O. Lewis Well No. 1

Well Location SW NW NE Sec. 21 Twp. 3-S Rge. # 32(E)-(W)

County Rawlins Field Name (if any) wildcat

Total Depth 4837 Oil Gas Dry Hole x

Was well log filed with application? yes . If not, explain:

Date and hour plugging is desired to begin September 11, 1953

Plugging of the well will be done in accordance with the Rules and Regulations
of the State Corporation Commission, or with the approval of the following excep-
tions: Explain fully any exceptions desired.

RECEIVED
STATE CORPORATION COMMISSION
09-19-1953
SEP 19 1953
CONSERVATION DIVISION
Wichita, Kansas

(Use an additional sheet if necessary)

Name of the person on the lease in charge of well for owner Stanton Cox, Jr

Address 1009 Central Building, Wichita, Ks

Name of Plugging Contractor Drilling Department of Natural Gas and Oil Corp

Address 1009 Central Building, Wichita 2, Kansas

Invoice covering assessment for plugging this well should be sent to Natural Gas
and Oil Corporation Address 1009 Central Building, Wichita, Ks

and payment will be guaranteed by applicant.

Harold A. Burt
Applicant or Acting Agent

Date September 17, 1953

PLUGGING
FILE SEC 21 T 3 R 32
BOOK PAGE 129 LINE 17

15-153-00009-00-02

DRILLER'S LOG

COMPANY: Natural Gas & Oil Corporation
and Ashland Oil and Refining Co

CONTRACTOR: Drilling Department of
Natural Gas and Oil Corporation

FARM: W. O. Lewis #1, SW NW NE Sec. 21-3S-32W,
Rawlins County, Kansas

COMMENCED: August 25, 1953

COMPLETED: September 11, 1953

0	to	70	Silt and clay	Elevation 3018 RB
70	to	185	Water sand and rotten lime	
185	to	207	Shale	
207	to	225	Shale and shells	Set Surface.
225	to	1775	Shale and shells	
1775	to	1930	Sand	
1930	to	2360	Shale and sand	
2360	to	2400	Shale and shells	
2400	to	2610	Shale and lime	
2610	to	2650	Red bed	
2650	to	2815	Shale and red bed	
2815	to	2835	Anhydrite	
2835	to	3312	Shale and shells	
3312	to	4024	Shale and lime	
4024	to	4074	Lime and shale	
4074	to	4245	Lime	
4245	to	4473	Shale and lime	
4473	to	4489	Conglomerate	
4489	to	4595	Lime and shale	
4595	to	4619	Chert-lime and shale	
4619	to	4647	Chert and lime	
4647	to	4670	Lime	
4670	to	4732	Cherty lime	
4732	to	4837	Lime	
		4837	T. D. Rotary	

RECEIVED
STATE CORPORATION COMMISSION
SEP 19 1953
09-19-1953
CONSERVATION DIVISION
Wichita, Kansas

Set 225 feet of 8 5/8" surface pipe. Cemented with 250 sacks cement and 4 sacks calcium chloride.

TOPS:	Fort Hays	1280	Anhydrite	2798	Marmaton	4294
	Codell sand	1380	Heebner	3974	Cherokee	4391
	Greenhorn	1595	Toronto	4004	Mississippi	4585
	Dakota	1710	Lansing	4013	Arbuckle	4686
			Base KC	4250		

DRILL STEM TESTS:

#1 3984-4024, open 1 hour, rec. 70' mud, 0 BHP.
#2 4024-74, open 1 hour, rec. 20' mud, 320# BHP.

Ran Schlumberger to 4834.
DRY, PLUGGED AND ABANDONED

C E R T I F I C A T E

I, Harold A. Burt, do hereby certify that the above and foregoing is a true and correct copy of the log of the W. O. Lewis #1, SW NW NE Section 21-3S-32W, Rawlins County, Kansas, as reflected by the files of the Natural Gas and Oil Corporation.

Harold A. Burt
Harold A. Burt

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 18th day of September, 1953.

Esther Unsell
Esther Unsell, Notary Public

My commission expires May 25, 1957.

PLUGGING
FILE SEC 21 T 3 R 32W
BOOK PAGE 129 LINE 17



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

September 16, 1953

15-153-00009-00-00

Well No.	1
Lease	Lewis
Description	SW 1/4 NE Sec. 31-3-32W
County	Rawlins
File No.	129-17

Natural Gas & Oil Corporation
1009 Central Bldg.,
Wichita, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY: J. P. Roberts
J. P. ROBERTS

cc: District Plugging Supervisor