

P

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20037-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name W. W. Sauvage Oil Company,

Complete Address: Oberlin, Kansas.

Lease Name Keith Sauvage Well No. 1

Location SW-SW-SW Sec. 11 Twp. 3 Rge. (E) (W) 29

County Decatur Total Depth 3945'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 12:30 PM Day 9 Month 2 Year 1968

The Above well was plugged as follows:

104'--8 5/8" Surface pipe, cement circulated.  
Dakota section from 1300' to 1500'. Land owner requests well to be left open as a potential fresh water well.

Circulated hole with heavy mud. Pulled DP to 1525' and displaced 100 Sx. cement thru DP from 1525' to 1200'. Pulled DP to 215' and displaced 30 Sx. cement thru DP from 215' to 85'. Left top plug out at request of land owner. (Water well Authorization attached).

Checked cement in well 2/10/68. Found top of cement @ 87'. (Cementing operations performed by Globe Oil Well Cementing, Incorporated).

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 14 1968  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 2-14-68

INV. NO. 7267-W

2-14-68

State of Kansas



15-039-20037-00-00

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

AUTHORIZATION

The undersigned, owner of the following described land, to wit: SW-SW-SW of Sec. 11 Twp. 3 Rge. 29 <sup>X</sup> W Decatur County, Kansas; hereby requests that Well No. 1 located in SW-SW-SW of Sec. 11 Twp. 3 <sup>X</sup> Rge. 29 W be left open above the fresh water protecting 1525' ~~1200'~~ to 1200' and 215' to 87' bridge set at \_\_\_\_\_ feet, to be used as a fresh water well and I hereby authorize W. W. Sauvage Oil Co., well owner, to so complete the abandonment of said well.

Witnessed by Allen Beall Keith Sauvage  
(Land Owner)

Dated at Oberlin, Kansas, this 12 day of February, 1968.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 14 1968  
CONSERVATION DIVISION  
Wichita, Kansas

2-14-68

