

14
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-30143-00-00

RECEIVED
STATE CORPORATION COMMISSION

SEP 10 1963
9-10-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Bishop Well No. 1

Location CSW-SW Sec. 14 Twp. 3 Rge. (E) (W) 35

County Rawlins Total Depth 4745

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 4:15 AM Day 7 Month 9 Year 1963

The Above well was plugged as follows:

183' --8 5/8" Surface pipe, cement circulated with 150 Sx.
Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.
cement thru DP. Heavy mud to 180', set plug with 1/4 Sk. hulls and dis-
placed 20 Sx cement thru DP. Heavy mud to 40', set plug with 1/2 Sk. hulls
and 10 Sx cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/10/63
INV. NO. 4921-W

Signed: *H. L. Nichols*
Well Plugging Supervisor