

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-133-20184-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1974
CONSERVATION DIVISION
Wichita, Kansas

10-11-74

Operator's Full Name Abercrombie Drilling Company, Incorporated,
Complete Address 801 Union Center, Wichita, Kansas.
Lease Name Wright Well No. 1
Location NE-NE Sec. 14 Twp. 3 Rge. (E) (W) 35
County Rawlins Total Depth 4640'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 9:15 PM Day 6 Month 10 Year 1974

The above well was plugged as follows:

296'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1575'.

Circulated hole with heavy mud. Pulled DP to 1800' and displaced 110 Cu. Ft. cement
thru DP from 1800' to 1475'. Pulled DP to 300' and displaced 30 Cu. Ft. cement thru
DP from 300' to 225'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/11/74
INV. NO. 91-W