

KANSAS

2

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20028-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address: Box #797, Great Bend, Kansas.

Lease Name Enfield Well No. 1

Location CNW-NW Sec. 19 Twp. 3 Rge. (E) (W) 35

County Rawlins Total Depth 4225

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 7:30 AM Day 8 Month 8 Year 1968

The Above well was plugged as follows:

328'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 1975'.

Circulated hole with heavy mud. Pulled DP to 2200' and displaced 100 Sx. cement thru
DP from 2200' to 1875'. Pulled DP to 335' and displaced 20 Sx. cement thru DP from
335' to 275'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

AUG 14 1968

CONSERVATION DIVISION
Wichita, Kansas

Signed: W. L. Nichols

Well Plugging Supervisor

INVOICED

DATE 8/14/68
INV. NO. 8279-W

8-14-68