

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-153-01001-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1963
11-18-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Beeson Well No. 1

Location CSW-SW Sec. 18 Twp. 3 Rge. (E) (W) 35

County Rawlins Total Depth 4890'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Barnes & Sons Pipe Pulling Company,

Address: 1450 Maple, Russell, Kansas License No. 9

Operation Completed: Hour 5:30PM Day 13 Month 11 Year 1963

The Above well was plugged as follows:

309' -- 8 5/8" Surface pipe, cement circulated with 25 Sacks.
4768' -- 5 1/2" cemented with 150 Sx. Plugged back to 4470', Top perforations
4230' to 4236'.

Sanded well back to 4920' and set 5 Sx. cement with dump bailer.
Pulled 5 1/2" to 720' and circulated heavy gel mud (29 Sacks). Pulled 5 1/2" to
630' and displaced 20 Sx cement thru 5 1/2". Pulled 5 1/2" to 300' and displaced
20 Sx. cement thru 5 1/2". Pulled 5 1/2" set rock bridge @ 30' and 10 Sx cement
to bottom of cellar.

(Cementing & Mudding operations performed by Globe Oil Well Cementing, Inc.)

I hereby certify that the above well was plugged as herein stated.

DATE 11/18/63
INV. NO. 8118-W

Signed: H. A. Nichols
Well Plugging Supervisor