


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

15-153-20056-00-00 Form CP-4

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rawlins County, Sec. 34 Twp. 3S Rge. 34 ~~XX~~ W (W)

Location as "NE/CNW/SW" or footage from lines 150' South of C NW NE

Lease Owner MACK OIL CO.

Lease Name Reinert Well No. 1

Office Address 812 Union Center Bldg., Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 2 19 69

Application for plugging filed September 2 19 69

Application for plugging approved September 3 19 69

Plugging commenced September 3 19 69

Plugging completed September 3 19 69

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey, Hays, Kansas

Producing formation None Depth to top Bottom Total Depth of Well 4560 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged with 70 sacks cement @ 1600'

20 sacks cement @ 180'

10 sacks cement @ 40'

Plugging completed: 11:30 a.m., September 3, 1969

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 5 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Thomas Drilling Company  
Address P. O. Box 400, Duncan, Oklahoma 73533


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Robert L. Harris

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Robert L. Harris*

812 Union Center Building, Wichita, Kansas  
(Address)

sworn to before me this 3rd day of September, 19 69



*Elizabeth F. Nice*  
Elizabeth F. Nice, Notary Public.

15-153-20056-00-00

MACK OIL CO.  
Duncan, Oklahoma  
73533

RECEIVED  
STATE CORPORATION COMMISSION  
09-05-1969  
SEP 5 1969  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLERS WELL LOG

#1 Reinert

150' South of C NW NE  
Section 34-3S-34W  
Rawlins County, Kansas  
Elevation: 2974' Kelly Bushing  
Initial Production: Dry  
Contractor: Thomas Drilling Co.

Commenced R. D.: 8-26-69  
Completed R. D.: 9- 2-69  
Rotary Total Depth: 4560'

STRATA	DEPTH
Surface Soil & Shale	0 - 360'
Shale	360 - 730
Shale & Sand	730 - 2069
Shale & Lime Streaks	2069 - 2455
Shale & Lime	2455 - 3044
Shale, Lime & Sand	3044 - 3325
Lime	3325 - 3465
Shale, Lime & Chert	3465 - 3658
Lime	3658 - 3756
Lime & Shale	3756 - 3952
Lime	3952 - 4560' - R. T. D.

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

MACK OIL CO.

By Robert L. Harris  
Robert L. Harris

Signed and sworn to in my presence this 4th day of September, 1969, by Robert L. Harris, representative of Mack Oil Co.

Elizabeth F. Nice  
Elizabeth F. Nice, Notary Public

My commission expires  
September 21, 1972

