


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

15-158-05158-00-00  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rawlins County.

Sec. 10 Twp. 35 Rge. (E) 34 (W)

Location as "NE/CNW/SW" or footage from lines NE-NW-NW

Lease Owner Mountain States Oil & Uranium & Stearns Petroleum, Inc.

Lease Name Samson Well No. 1

Office Address \_\_\_\_\_

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed October 4 19 55

Application for plugging filed \_\_\_\_\_ 19 \_\_\_\_\_

Application for plugging approved \_\_\_\_\_ 19 \_\_\_\_\_

Plugging commenced October 4 19 55

Plugging completed October 4 19 55

Reason for abandonment of well or producing formation Lost circulation at 4668'  
Arbuckle. Further drilling impractical.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4668 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

8-5/8 Surface pipe set at 185'  
Cemented with 100 sacks cement.  
Plug with mud to 180'.  
Halliburton 8-5/8 plug at 180' with 1/2 sack hulls-15sacks cement.  
Halliburton 8-5/8 plug at 40' with 1/2 sack hulls -- Cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stearns Petroleum, Inc.

Address Box 313, Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.

R. V. Appling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Field Superintendent

(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 19 55

My commission expires April 5, 1958

Betty Lou Miller  
**REC Lou Miller**  
Notary Public.  
STATE CORPORATION COMMISSION

**PLUGGING**  
FILE SEC 10 T 3 R 316  
BOOK PAGE 6 LINK 26

NOV 12 1955  
11-12-1955  
CONSERVATION DIVISION  
Wichita, Kansas

