

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

15-153-30141-00-00

Rawlins County. Sec. 27 Twp. 3 Rge. 33 (E)W (W)

Location as "NE/CNW/SW" or footage from lines NE SE NE
Lease Owner Harms-Burt Drilling Company
Lease Name Reeh Well No. 1
Office Address P.O. Box 488 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 21 19 62
Application for plugging filed March 21 19 62
Application for plugging approved March 21 (verbally) 19 62
Plugging commenced March 21 19 62
Plugging completed March 21 19 62
Reason for abandonment of well or producing formation Dry Hole

NORTH

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4674 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	245'	8 5/8"	245'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 550' then plug and 20 sacks of cement, heavy mud to 180' with plug and 20 sacks of cement. Heavy mud to 40' with plug and 10 sacks of cement at this point.

RECEIVED
STATE CORPORATION COMMISSION
MAR 27 1962
03-27-1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Harms Drilling Company
Address P.O. Box 488 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
ALLAN HARMS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allan Harms
P.O. Box 488 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26 day of March, 19 62

Eldon E. Gerhart
Notary Public.

My commission expires January 22, 1966



D R I L L E R S L O G

Company: Harms-Burt Drilling Company
Farm: Reeh # 1
Commenced: March 10, 1962
Elevation: 3092 KB

NE SE NE Section 27-3S-33W
Rawlins County, Kansas
Completed: March 21, 1962

15-153-30141-00-00

0 - 180	shale
180 - 200	sand
200 - 236	shale
236 - 2000	shale-sand streaks
2000 - 2050	shale
2050 - 2310	shale-sand
2310 - 2380	sand
2380 - 2545	shale-sand
2545 - 2590	anhydrite
2590 - 2640	Red bed
2640 - 2840	shale-red bed
2840 - 2876	anhydrite
2876 - 3230	shale-shells
3230 - 3536	shale-lime
3536 - 3610	lime-shale
3610 - 3670	shale-lime
3670 - 3955	lime-shale
3955 - 4430	lime
4430 - 4552	lime & shale
4552 - 4674	lime, shale & sand
4674	Total depth

RECEIVED
STATE CORPORATION COMMISSION
MAR 27 1962
CONSERVATION DIVISION
Wichita, Kansas

Set 245' of 8 5/8" surface pipe. Cemented with 175 sacks of cement with 2% calcium chloride.

Tops:	Anhydrite	-	2545
	Heebner	-	4027
	Lansing	-	4065
	Base K.C.	-	4300
	Marmaton	-	4300
	Cherokee	-	4508
	Mississippi	-	4647

Drill Stem Tests: #1 4037 - 4105 Open 1 1/2 hr. 20 minutes shut in. Recovered 120' oil spotted mud 120' salt water IBHP - 1270# FBHP - 1100#

Ran electric log.

Dry, plugged, and abandoned.

A F F I D A V I T

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

I, Allan Harms of the Harms-Burt Drilling Company being first duly sworn on oath state: I have knowledge of the facts, statements and matters herein contained and the same are true and correct.

Allan Harms
Allan Harms

Subscribed and sworn to before me this 26 day of March, 1962.

Helen E. Gearhart
Helen E. Gearhart Notary Public

My commission expires January 22, 1966