


15-153-20139-00-04

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rawlins County, Sec. 11 Twp. 3 Rge. 33 (E) (W)
Location as "NE/CNWKSWA" or footage from lines SW NW NW
Lease Owner Murfin Drilling Company
Lease Name Fikan Trust #1 Well No. _____
Office Address Russell, Kansas 67665
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9/6/73 _____ 19____
Plugging completed 9/10/73 _____ 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4354 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8 | 128 | none |
| | | | | 5 1/2" | 4389 | 1425' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, pushed plug to 3600' and ran sand to 3550'.
Dumped 5 sacks cement. Loaded hole, shot pipe at 3024', 1803'
1614', ~~159~~ 1519', 1426', pulled 45 joints. Allied squeezed
well with 5 sacks hulls, 11 sacks gel, 110 sacks cement, 34 sacks
gel and 50 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
SEP 19 1973
09-19-1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. Darrell Kelso ~~NOTARY PUBLIC~~ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of Sept., 1973

My commission expires _____
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

WELL LOG

15-153-20139-00-00

COMPANY MURFIN DRILLING COMPANY

SEC. 11 T. 3S R. 33W

FARM Fikan Trust #1 NO. 1

LOC.


RIB. NO. 8

TOTAL DEPTH 4390'

COMM. 6-23-72

COMP. 7-2-72

COUNTY Rawlins KANSAS



CONTRACTOR Murfin Drilling Company

CASING

20 10
15 8 5/8" 128' w/125 SX
12 6
13 5 1/2" 4389' w/285 SX

ELEVATION 2846 GL 2851 KB

PRODUCTION Oil

FIGURES INDICATE BOTTOM OF FORMATIONS

ANH 2601' (+250)
B/ANH 2635' (+216)
WAB 3307' (-456)
TOP 3633' (-782)
OR 3740' (-889)
HEEB 3755' (-904)
DOUG 3767' (-916)
L/KC 3796' (-945)
B/KC 4046' (-1195)
FT. SCOTT 4061' (-1210)

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1973
08-30-1973
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas
County of Sedgwick } ss:

I, James R. Daniels of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Fikan Trust #1 well.

James R. Daniels/General Manager

Subscribed and sworn to before me this 4th day of August 1972

My Commission Expires: Aug 29 1973

NOTARY PUBLIC

