

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 153-20522-00-00

SW, Sec. 27, T 3 S, R 36 W/2

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8762

Lease Name Cahoj Well # 27-14A

Operator: magnus oil co.
Name &

County Rawlins

Address Arapaho Nebr.

Well Total Depth 4759 feet # 154.67

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 382

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Moxa Drilg. Co. License Number 8762

Address McCook Nebr. 106 W 8th

Company to plug at: Hour: 3 AM Day: 25 Month: 11 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Darold Demar

(company name) moxa Drilg ³⁰⁸ (phone) 345-2945

were: order 195 sx cem. 50/50 portmix 6% gel. 3% c.c.

1sx hulls 1- 8 5/8 plug 1sx Flow seal

Heavy mud between all plugs.

pump cem. down drill pipe.

Elev. 3303 Anhydrite 3119.42 Arbuckle No.

Dakota- 1200
2103 = 2400

Signed Dale Balthazor
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part (None)

Operations Completed: Hour: 2:45 PM Day: 25 Month: 11 Year: 1983

ACTUAL PLUGGING REPORT circ. @ 3130 Turn hole over

25 SX @ 3130

100 SX @ 2400 mix with 1sx flow seal.

40 SX @ 430 1sx hulls. push plug to 40'

10 SX @ 40

10 SX in Rat hole

10 SX in mouse hole

Remarks: _____

cementing to sun.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / (did not)) observe this plugging.

INVOICED

DATE 12-29-83

INV. NO. 7267-W

Signed Dale Balthazor
STATE CORPORATION COMMISSION (TECHNICIAN)

DEC 5 1983
12-5-83

CONSERVATION DIVISION
WICHITA, KANSAS