

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-153-20139-00-04

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1973
09-13-1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center, Wichita, Kansas 67202

Lease Name Fikam Trust Well No. 1

Location SW NW NW Sec. 11 Twp. 3 Rge. (E) (W) 33

County Rawlins Total Depth 4390'

Abandoned Oil Well Gas Well Input Well SWD Well Lead D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 12 N Day 10 Month 9 Year 1973

The above well was plugged as follows:

Total Depth 4390' 8 5/8 csg set at 128' cwc 125 sk.

5 1/2 csg set at 4389' cw 285 sk.

5 1/2 csg PBTD 4354' with perf. (3823')

Set 5 1/2 wood plug at 3600' -poured 15' sand -dumped 5 sk cmt W/dump bailer. (3550-3600)

Cutoff and recovered 1426' of 5 1/2 csg.

Pumped down 8 5/8 csg with 5 sk hulls--11 sk gel--110 cu ft cem--34 sk gel--

released 8 5/8 plug and pumped 50 cu ft of cem. by Allied Cementing Co. SIP 400 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Murrin
Well Plugging Supervisor

INVOICED

DATE 9-13-73

INV. NO. 7910-10