

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-153-20179-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 4 1974  
06-04-1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Clinton Oil Company,

Complete Address Box #1201, Wichita, Kansas.

Lease Name C. A. Walker Well No. 1-V

Location CNW-SE Sec. 17 Twp. 3 Rge. (E) (W) 33

County Rawlins Total Depth 4105'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.     

Operation Completed: Hour 9:30 PM Day 30 Month 5 Year 1974

The above well was plugged as follows:

257'--8 5/8" Surface casing, cement circulated with 250 Sx.

Top of Dakota section @ 1600'.

Circulated hole with heavy mud. Pulled DP to 1825' and displaced 110 Cu. Ft. cement  
thru DP from 1825' to 1500'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Dickel  
Well Plugging Supervisor

date 6/5/74  
INV. NO. 9243-W