

KANSAS

2
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-153-20142-00-00

RECEIVED
STATE CORPORATION COMMISSION
11-09-1972
NOV 9 1972

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Clinton Oil Company,
Complete Address 217 North Water, Wichita, Kansas.
Lease Name Elma Rogers Well No. 1-V
Location CNE-SW Sec. 10 Twp. 3 Rge. (E) (W) 33
County Rawlins Total Depth 4240'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Murfin Drilling Company,
Address 617 Union Center, Wichita, Kansas License No.
Operation Completed; Hour 10:00 AM Day 5 Month 11 Year 1972

The above well was plugged as follows:

208'-10 3/4" Surface casing, cement circulated with 200 Sx. (9" Hole)
Circulated hole with heavy mud. Pulled DP to 2025' and displaced 135 Cu. Ft. cement
thru DP from 2025' to 1700'. Pulled DP to 215' and displaced 35 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 15 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Dinkel*
Well Plugging Supervisor

INVOICED

DATE 11/9/72
INV. NO. 6606-w