

15-153-20053-00-00

R

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 18 1969  
08-18-1969  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Mack Oil Company,  
Complete Address 812 Union Center Building, Wichita, Kansas.  
Lease Name Kog1 Well No. 1  
Location SW-NE-NE Sec. 3 Twp. 3 Rge. (E) (W) 33  
County Rawlins Total Depth 4446'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated       
Plugging Contractor Thomas Drilling Company, Incorporated.  
Address Box #100, Duncan, Oklahoma. License No.       
Operation Completed: Hour 3:00 PM Day 15 Month 8 Year 1969

The above well was plugged as follows:

220'---8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1110'.

Circulated hole with heavy mud. Pulled DP to 1365' and displaced 120 Sx. cement thru  
DP from 1365' to 975'. Pulled DP to 250' and displaced 20 Sx. cement thru DP from  
250' to 190'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 8-18-69

INV. NO. 330-W

Signed: W. L. F. J. J. J.  
Well Plugging Supervisor