

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-153-19011-00-00

RECEIVED
STATE CORPORATION COMMISSION

DEC 12 1962

12-12-62

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Shamrock Oil & Gas Corp
Complete Address: Box 631 Amarillo, Texas
Lease Name Joe Bell Well No. 1
Location CSE SE Sec. Twp. 13 Rge. 3 (E) (W) 36
County Rawlins Total Depth 4760-4899'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Forbes Casing Pulling Co
Address: Great Bend, Kansas License No. 49
Operation Completed: Hour 12:15PM Day 10 Month 12 Year 62

The Above well was plugged as follows:

10 3/4" ~~3~~ 325' circulated with cement - 7" 4760' with 300 sax cement.
Perf 4425' - sand back above perforations and set 5 sax cement with
dump bailer.

Pulled 1630' 7" to 415' - circulated hole with heavy gel mud through
7" at 415' - (38 sax gel), displaced 25 sax cement through 7" at
310' - heavy mud to 35', set bridge and 10 sax cement to bottom
cellar.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/12/62
INV. NO. 6210-W

Signed: Edna Kelly
Well Plugging Supervisor