

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 17 1973  
10-17-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-153-20166-00-00

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Weishapl Well No. 1

Location SW-SW-SW Sec. 25 Twp. 3 Rge. (E) (W) 34

County Rawlins Total Depth 4195'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas License No.       

Operation Completed: Hour 3:00 PM Day 13 Month 10 Year 1973

The above well was plugged as follows:

2 1/4" - 8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1675'.

Circulated hole with heavy mud. Pulled DP to 1900' and displaced 110 Cu. Ft. cement  
thru DP from 1900' to 1575'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru  
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 10/17/73

Signed: H. L. Nichols  
Well Plugging Supervisor

INV. NO. 8025-42