

69

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-153-20125-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 12 1971  
10-12-1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name F & M Oil Company.

Complete Address 603 Union Center, Wichita, Kansas.

Lease Name Cloe Well No. 1

Location CSE-NW Sec. 10 Twp. 3 Rge. (E) (W) 34

County Rawlins Total Depth 4290'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Murfin Drilling Company.

Address 617 Union Center, Wichita, Kansas. License No.       

Operation Completed: Hour 8:00 AM Day 8 Month 10 Year 1971

The above well was plugged as follows:

229'--8 5/8" Surface casing, cement circulated with 125 Sx.  
Top of Dakota section @ 1775'.

Circulated hole with heavy mud. Pulled DP to 2000' and displaced 100 Sx. cement thru  
DP from 2000' to 1675'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from  
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Dichek  
Well Plugging Supervisor

INVOICED

DATE 10-13-71

INV. NO. 4469-W