

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20056-00-00

RECEIVED
STATE CORPORATION COMMISSION
09-05-1969
SEP 5 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mack Oil Company

Complete Address 812 Union Center Wichita, Kansas

Lease Name Reinert Well No. 1

Location C NW NE Sec. 34 Twp. 3 Rge. (E) (W) 34

County Rawlins Total Depth 4560'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Thomas Brillling

Address Wichita, Kansas License No.

Operation Completed: Hour 11:30A Day 3 Month 9 Year 1969

The above well was plugged as follows:

RTD 4560' 8 5/8 csg set at 197' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 1600' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/5/69
INV. NO. 409-W

Signed: Geo F. Messy
Well Plugging Supervisor