



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

15-153-20125-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 12 1971  
10-12-1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: F & M Oil Company, Incorporated,

Complete Address: 603 Union Center, Wichita, Kansas.

Lease Name: Cloe Well No. 1

Location: CSE-NW Sec. 10 Twp. 3 Rge. (E)(W) 34

County: Rawlins Total Depth 4290' Oil Well

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Sixbury was instructed to plug the well as follows:

229'--8 5/8" Surface casing, cement circulated with 125 Sx.  
Top of Dakota section @ 1775'.

Circulate hole with heavy mud. Pull DP to 2000' and displace 100 Sx.  
cement thru DP. Pull DP to 2450' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent